BILL OF QUANTITIES

ICF KIT · CONCRETE · LABOUR

LANGLEY LANE FARM, MIDDLETON

Single-storey dwelling, split-level GF, vaulted 35 deg roof · Langley Lane, Middleton M24 5LJ · ENGLAND

Quotation Reference	ES26-063
Project	Langley Lane Farm, Middleton
House Type	Single-storey dwelling: one 8in Standard footing course per floor zone + 6in XR35 GF walls (8 courses), raked gables, chimney stack and vault upstands; GF block & beam (by others); vaulted cut roof, slate / tile
Client	Mark Whalley - Ethos Property Development
Site Address	Langley Lane Farm, Langley Lane, Middleton M24 5LJ
BOQ Issued	02 November 2026
BOQ Reference	BOQ-ES26-063-001
Prepared by	Tom Smith — BuildEase Manager, Nudura UK
Issued by	Tremco Construction Products Group
Currency	Pound Sterling (GBP) · VAT at 20%
Measurement Convention	RICS New Rules of Measurement (NRM2)

IMPORTANT NOTICE — DISCLAIMER

- This Bill of Quantities is supplied in good faith based on the BuildEase take-off models for Langley Lane Farm, Middleton and the associated Tremco CPG quotation.
- ALL QUANTITIES SHOULD BE INDEPENDENTLY CHECKED AND VERIFIED BY THE PROJECT QS / QUANTITY SURVEYOR before tender submission, ordering or contract award.
- This BOQ does NOT include an external render / finish allowance. Any render, coatings or external wall finish must be measured and priced separately.
- Section C (Concrete) volumes are geometric voids — allow ~3% web displacement deduction and ~5% wastage on top when ordering ready-mix.
- Section D (Labour) day estimates are scaled proportionately from a reference project; actual gang productivity will vary with site conditions, weather and trade experience.
- BuildEase, Tremco Construction Products Group and Nudura UK accept no liability for tender or contract outcomes arising from the use of these figures. If in doubt — ask.
- Contact: Tom Smith — BuildEase Manager, Nudura UK — for clarification on any quantity or rate basis in this document.

ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector. ONE single-storey dwelling on a split-level ground floor (lower zone FFL 124.400 = datum 0: kitchen / dining / snug; upper zone FFL 125.000 = +600), vaulted 35 deg roof: the highest point is the chimney stack top at 6,541 above the lower FFL (ridge ~6,482, geometric) - ~6.7 m above the lowest ground (ground ASSUMED ~150 below each zone FFL - no survey), BELOW 11 m: the 11-18 m fire band does not apply. Approved Document J: the stove flue outlet height (1 m above the roof intersection, rooflights within 2.3 m) is an RFI to the stove installer. Single storey - inside the LABC Warranty 3-storey ICF cap.

ONLY the Nudura ICF formwork and associated accessories are in our price; everything else is supplied in good faith and must be checked by the relevant professional. NOT FOR CONSTRUCTION. The "floor" slot of the programme is the GF precast block & beam BY OTHERS (beams, blocks, insulation, screeds NOT in this ICF BOQ - coordination quantities in the finishes package Bill 6). Engineer to design: the indicative steels (UB ridges / purlins / hip / valley, PFC eaves beams over the NE set-back, SHS posts, the chimney stack lintel + trimmers), the oak trusses, the roof (unpropped hip / valley heads), the strip footing and the B&B bearings.

CONTENTS

Section	Description	Sheet	Status	
	Cover & Project Information	**Cover**		
	Contents	**Contents**		
	Indicative Programme (Gantt)	**Programme**	*Information*	
	Summary of Tender Pricing	**Summary**		
A	Preliminaries	**A_Preliminaries**	*Contractor priced*	
B	ICF Kit Supply	**B_ICF_Supply**	*Pre-priced*	
C	Concrete Supply, Pump & Placement	**C_Concrete**	*Contractor priced*	
D	Labour — ICF, Floors & Roofs	**D_Labour**	*Contractor priced*	
F	Reference Data (informative only)	**F_Reference**	—	

PROG · INDICATIVE INSTALL PROGRAMME — RESOURCE-LEVELLED, ONE COLUMN PER WORKING DAY

Group-by-group sequential build with a staggered start between groups. ICF install + snag + pour cycles, intermediate floors and roof structure are completed before moving on. Resourcing and durations below are indicative and must be validated by site management. Render / external finish is NOT included in this programme.

Group	Plots	Forms	Weeks	Start wk	W1 M	W1 T	W1 W	W1 T	W1 F	W1 S	W1 S	W2 M	W2 T	W2 W	W2 T	W2 F	W2 S	W2 S	W3 M	W3 T	W3 W	W3 T	W3 F	W3 S	W3 S
Langley Lane Farm	1	352	3	1																					

LEGEND

	ICF walls — first lift: FB footing courses, both zones (erection, snag & pour)
	ICF walls — L1 GF walls (after the GF B&B), then L2 gables / stack / upstands (after the L1 pour)
	Concrete pour — sized at 60 m3 per pump-day (1 day per lift here), ICF crew attends, pump on site
	Curing — pours held to Fridays where possible so the 2 curing days fall on the weekend; a mid-week pour cures 2 working days
	GF block & beam floor — after the FB pour (by others, 1 day by Tom's rule)
	Vaulted roof structure, after the L2 pour (1 day by Tom's rule)

RESOURCING

• 1 ICF crews of 8 trained installers (each crew = 2 four-man gang-equivalents) erect the wall lifts, moving to the next ready block while a floor is fitted; 1 joinery crew of 3 fits every intermediate floor and roof (Tom's rule 19.10.26: floors 1 day per plot, roofs 1 day per plot - one plot; the 'floor' here is the GF precast block & beam (by others - programme slot, the joinery crew attends), the roof is the vaulted cut roof). Programme is resource-levelled day by day (white = block waiting for a crew).

• Total ICF site programme: 3 working weeks (ICF erection, floors and roofs). Section A Preliminaries are quantified against this 3-week programme.

• EXTERNAL RENDER / FINISH IS EXCLUDED from this BOQ and this programme. Where a render system is later specified, allow a separate workstream — per BBA guidance, render cannot begin until the concrete core has cured for a minimum of 28 days after the final pour.

• Concrete pump booked on the pour days for each group (see Section C).

• Lead time for BuildEase Pre-Cut Service: 5–6 weeks from order placement; procurement runs in parallel with mobilisation.

• Programme estimates are provided in good faith and must be verified by the project / site management team.

• ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector. ONE single-storey dwelling on a split-level ground floor (lower zone FFL 124.400 = datum 0: kitchen / dining / snug; upper zone FFL 125.000 = +600), vaulted 35 deg roof: the highest point is the chimney stack top at 6,541 above the lower FFL (ridge ~6,482, geometric) - ~6.7 m above the lowest ground (ground ASSUMED ~150 below each zone FFL - no survey), BELOW 11 m: the 11-18 m fire band does not apply. Approved Document J: the stove flue outlet height (1 m above the roof intersection, rooflights within 2.3 m) is an RFI to the stove installer. Single storey - inside the LABC Warranty 3-storey ICF cap.

• Tom's rule (19.10.26): floors 1 day PER PLOT, roofs 1 day PER PLOT - one plot here, so the GF block & beam slot and the vaulted roof are shown at 1 day each. The floor row of this programme is the GF PRECAST BLOCK & BEAM BY OTHERS (beam supplier / groundworker; the joinery crew attends): lower zone 150 B&B + 150 insulation + 82 screed, upper zone 150 B&B + 150 insulation + 75 screed. The beams bear on the 8in Standard footing course (150 cut off its INSIDE face at the bearing - ICF erector coordination). Beams, blocks, insulation, screeds and craneage are NOT in this ICF BOQ (coordination quantities in the finishes package Bill 6).

- Build sequence (no client programme issued): FB (one 8in Standard footing course in each floor zone - FB-Lower and FB-Upper, on the strip footing by others) -> pour -> GF block & beam floor (both zones) -> L1 GF walls (6in XR35, 8 courses to the underside of the plate at 3,341) -> pour -> L2 (raked gables, the chimney stack to 6,541 over the flue on its steel lintel / trimmers, the NE vault upstands) -> pour -> vaulted roof (C24 @ 400 cut roof on UB ridges / purlins, oak arched trusses A1-A3).

- ICF pours sized at 60 m3 per pump per day from each lift's own concrete volume (every pour is 1 pump day here).

- PROGRAMME (BOQ Builder sheet 'Programme', 1 ICF crew of 8 + 1 joinery crew of 3, Tom's rule floors / roofs 1 day per plot, pours at 60 m3 / pump-day, 2 days cure): 15 working days = 3 weeks. Sequence: ICF FB d0-0.42; pour d1-2; cure d2-4; GF B&B floor d4-5; ICF L1 d5-7.32; pour d9-10; ICF L2 d10-10.61; pour d11-12; cure d12-14; roof d14-15. ICF concrete 53.33 m3 (geometric, 352 ordered forms: FB 8.35 / L1 35.97 / L2 9.01) in 3 pump days. ALIGNMENT: the proposal prices 4 stillages x 5 weeks hire (GBP 1,600.00); on this programme the alignment is needed from the first ICF lift (FB, day 0) to the last pour (L2, day 12) = 3 weeks on hire - 2 weeks LESS than priced (GBP 640.00 of hire not needed on this programme). The proposal has NOT been changed - confirm the hire period with the client / site team.

- Site access: Langley Lane, Middleton (rural lane) - 18 t rigid wagon delivery access and unloading by the contractor for the 2 deliveries (17 pallets + 4 alignment stillages); a transfer to smaller vehicles is not included.

SUMMARY OF TENDER PRICING

Section totals are carried forward from each Bill section. Pre-priced columns show values from the associated Tremco CPG quotation; contractor-priced columns populate automatically when rates are entered in the section sheets. This BOQ excludes external render.

Section	Description	Pre-priced (£)	Contractor-priced (£)	Section Total (£)	
A	Preliminaries		£0.00	**£0.00**	
B	ICF Kit Supply	£24,103.56		**£24,103.56**	
C	Concrete Supply, Pump & Placement		£0.00	**£0.00**	
D	Labour — ICF, Floors & Roofs		£0.00	**£0.00**	
	NET TOTAL (excluding VAT)	**£24,103.56**	**£0.00**	**£24,103.56**	
	VAT @ 20%			£4,820.71	
	GRAND TOTAL (inclusive of VAT)			**£28,924.27**	

SIGNATURES

Priced by					
Tendered by					
Approved by					

A · PRELIMINARIES

Items priced per working week against the site programme total of 3 weeks (see Programme sheet). Quantities are pre-populated; the contractor inserts the weekly rate.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
A.1	Site set-up, fencing, signage, induction & welfare establishment	item	1		£0.00
A.2	Welfare facilities — canteen, drying, toilets (hire)	wk	3		£0.00
A.3	Contract management & site supervision	wk	3		£0.00
A.4	Health & Safety, RAMS, CDM consultancy	wk	3		£0.00
A.5	Public liability and contract works insurance	item	1		£0.00
A.6	Scaffolding — independent access for ICF erection	wk	3		£0.00
A.7	Plant hire — telehandler / forklift for offload & ICF moves	wk	3		£0.00
A.8	Plant hire — small tools, generators, power & lighting	wk	3		£0.00
A.9	Hoarding / site enclosure / security	wk	3		£0.00
A.10	Temporary services — water, power, lighting (hire)	wk	3		£0.00
A.11	Site clean, waste management & skip rotation	wk	3		£0.00
A.12	Setting out and surveying — engineer's level checks	wk	3		£0.00
A.13	Site take-down, hand-over & demobilisation	item	1		£0.00
A.14	Pre-completion sound test (Approved Document E)	test			£0.00
A.15	Air-tightness test (Approved Document L)	test			£0.00
A.16	Day works allowance	sum			£0.00
	A — PRELIMINARIES SUBTOTAL				**£0.00**

B · ICF KIT SUPPLY

ICF material supply values are pre-priced from the associated Tremco CPG quotation. Pre-cut service fees are taken from each BuildEase take-off.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
B.1 — ICF Block, Forms & Accessories					
B.1	ICF Materials — Langley Lane Farm (1 plot(s), 352 forms)	group	1	£18,710.85	£18,710.85
B.2 — BuildEase Pre-Cut Service Fee					
B.2	Pre-Cut Service — Langley Lane Farm	group	1	£2,624.69	£2,624.69
B.3 — Haulage					
B.3	Haulage to site — ESTIMATE - 3 loads: 3 x rigid (18 t) @ 80.0 mi (proposal delivery schedule: FB + L1, then L2); final haulage confirmed on order with the agreed delivery schedule	item	1	£1,168.02	£1,168.02
B.4 — Alignment System					
B.4	Alignment System Rental — Langley Lane Farm (67 systems)	group	1	£1,600.00	£1,600.00
	B — ICF KIT SUPPLY SUBTOTAL				**£24,103.56**

C · CONCRETE SUPPLY, PUMP & PLACEMENT

Volumes are geometric void calculations (block length × course height × core thickness). Allow ~3% for plastic web displacement and ~5% wastage when ordering. Rates to be inserted by the contractor.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
C.1 — Ready-Mix Concrete Supply (C28/35 typical to BS 8500)					
C.1	Ready-mix concrete — Langley Lane Farm (1 plot(s), geometric void)	m³	53.33		£0.00
C.2 — Concrete Pump Hire					
C.2	Boom pump hire — Langley Lane Farm	day	3		£0.00
C.2	Pump mobilisation / demobilisation	item	1		£0.00
C.3 — Concrete Vibration & Placement Plant					
C.3	Internal poker vibrator hire — site duration	wk	3		£0.00
C.3	Concrete banksman / poker operator	day			£0.00
	C — CONCRETE SUBTOTAL				**£0.00**

D · LABOUR — ICF INSTALL, FLOORS & ROOFS

ICF install days scaled proportionately against the Maycroft reference (52.65 forms per gang-day). Rates below are per 4-man gang per day. Floor and roof allowances are taken per group from the project configuration.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
D.1 — ICF Install Gang					
D.1	ICF install — Langley Lane Farm (352 forms ÷ 52.65 forms/day = 6.7 gang-days)	gang-day	6.70		£0.00
D.1	Snag, pour & cure attendance (30% allowance, project total)	gang-day	2.00		£0.00
D.2 — GF Floor (precast block & beam BY OTHERS, both floor zones - a 1-day programme slot by Tom's rule; joinery crew attends)					
D.2	GF block & beam by others (programme days) — Langley Lane Farm (1 floor × 1 gang-days)	gang-day	1		£0.00
D.3 — Roof Structure Labour (vaulted cut roof: C24 47 x 245 @ 400 on UB ridges / purlins, oak arched trusses A1-A3)					
D.3	Roof structure — Langley Lane Farm	gang-day	1		£0.00
	D — LABOUR SUBTOTAL				**£0.00**

F · REFERENCE DATA (informative only)

Per-group quantities calculated from the BuildEase take-off models. Values feed into Sections C and D. Render is excluded from this BOQ.

Group	Plots	Forms	Concrete (m³)	ICF install days	Floor + Roof days	Pre-cut (£)
Langley Lane Farm	1	352	53.33	6.70	2	£2,624.69
SITE	**1**	**352**	**53.33**	**6.70**	**2**	**£2,624.69**

PER-LIFT FORM BREAKDOWN

Group	Lift	4" Std	6" XR35 str	6" XR35 cnr	8" Std	Lift total
Langley Lane Farm	FB	0	0	0	44	44
Langley Lane Farm	L1	0	147	97	0	244
Langley Lane Farm	L2	0	31	33	0	64

GEOMETRIC CONSTANTS & CALCULATION BASIS

Block length	2.438 m	*96 inches*
Course height	0.4574 m	*18 inches*
4" Std straight volume	0.1133 m³	*Volume = length × course × core*
6" XR35 straight volume	0.1699 m³	*Volume = length × course × core*
8" Std straight volume (FB footing courses)	0.2266 m³	*Volume = length × course × core*
4" Std corner volume	0.0511 m³	*L-void; long 31.625" / short 15.625"*
6" XR35 corner volume	0.1133 m³	*L-void; long 43" / short 27"*
Maycroft install rate	52.65 forms/day	*Reference: 1053 forms ÷ 20 days*

Bill of Quantities Package - Finishes & Ancillary Trades

ES26-063 | Langley Lane Farm, Middleton | Mark Whalley - Ethos Property Development

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Project	Langley Lane Farm, Middleton
Site	Langley Lane Farm, Langley Lane, Middleton M24 5LJ
Client	Mark Whalley - Ethos Property Development
Drawings	The client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026
Quotation ref	ES26-063
Document	Bill of Quantities Package - Finishes & Ancillary Trades
Date	02/11/2026
Scope	One single-storey dwelling on a split-level ground floor (lower zone kitchen / dining / snug, upper zone the rest incl. the SE bedroom wing): one 8in Standard ICF footing course per zone + 6in XR35 GF walls, raked gables, a chimney stack and NE vault upstands; GF precast block & beam by others; vaulted 35 deg cut roof on steels with oak arched trusses, slate / tile, rooflights; vertical timber cladding; alu-clad RAL 7016 glazing screens, lift-and-slide and composite doors
Building height	**ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector. ONE single-storey dwelling on a split-level ground floor (lower zone FFL 124.400 = datum 0: kitchen / dining / snug; upper zone FFL 125.000 = +600), vaulted 35 deg roof: the highest point is the chimney stack top at 6,541 above the lower FFL (ridge ~6,482, geometric) - ~6.7 m above the lowest ground (ground ASSUMED ~150 below each zone FFL - no survey), BELOW 11 m: the 11-18 m fire band does not apply. Approved Document J: the stove flue outlet height (1 m above the roof intersection, rooflights within 2.3 m) is an RFI to the stove installer. Single storey - inside the LABC Warranty 3-storey ICF cap.**
Engineer / specialists	**ENGINEER / SPECIALISTS TO DESIGN: STRUCTURAL ENGINEER: the indicative steels (UB 203 x 133 ridges / purlins / hip / valley, PFC 180 x 75 eaves beams over the NE set-backs, SHS 100 posts incl. the mullion posts in the lift-and-slide openings, the chimney-stack lintel + trimmers on 2 SHS posts); padstones / pockets in the ICF core (form at the pour); the roof (4 hip / valley heads with no prop in the model; the 16 m wing ridge as a steel); the oak trusses A1-A3; the strip footing (stepped at the zone change); the B&B bearings on the footing course and the step walls. NOT FOR CONSTRUCTION.**
Prepared by	BuildEase (Tremco CPG UK) - BuildEase Design Suite quotation model
Status	**FOR INFORMATION, COORDINATION AND PRICING BY OTHERS - rates blank; NOT part of the Nudura ICF price; NOT FOR CONSTRUCTION**

PACKAGE OVERVIEW - pricing by others (all amounts formula-linked to each bill's Package Summary)

Bill	Package	Code / NRM2	Supply £	Install £	Total £
Bill 1	External Wall Cladding to the ICF (vertical timber cladding, plinth, trims, stack, feature brick / stone)	EXT NRM2 14 / 16	£0.00	£0.00	£0.00
Bill 2	Internal Linings - ICF Faces, Partitions, Vaulted Ceilings, Tape, Beads & Skim	DRY NRM2 28	£0.00	£0.00	£0.00
Bill 3	Internal Doors, Cupboard Doors & Ironmongery (per leaf)	JOI NRM2 24	£0.00	£0.00	£0.00
Bill 4	Joinery - Skirtings, Architraves, Window Boards, Steps & Sundries	JOI NRM2 22	£0.00	£0.00	£0.00
Bill 5	Internal Partitions - Blockwork TYPE A / B and Timber Studs TYPE C / D	MAS / JOI NRM2 14 / 16	£0.00	£0.00	£0.00
Bill 6	Substructure and GF Block & Beam Floor, both zones (coordination)	GRW / FLR NRM2 5 / 11 / 14	£0.00	£0.00	£0.00
Bill 7	Roof - Vaulted Cut Roof, Steels, Oak Trusses, Covering, Rooflights, Rainwater & Insulation	RFS / STR / RFC NRM2 14 / 16 / 18	£0.00	£0.00	£0.00
Bill 8	Opening Schedule - Windows, Glazing Screens & External Doors (one line per opening)	WIN NRM2 25	£0.00	£0.00	£0.00
	GRAND TOTAL - finishes / ancillary trades, net (excl. VAT)		**£0.00**	**£0.00**	**£0.00**

Optional additions (enter %; blank = 0)		**%**	**Amount £**
Preliminaries	on the finishes net grand total		£0.00
Overheads & profit	on net total + preliminaries		£0.00
Contingency	on net total + preliminaries + OH&P		£0.00
	GRAND TOTAL finishes incl. preliminaries, OH&P and contingency (excl. VAT)		**£0.00**

ICF PACKAGE HOOK - BuildEase BOQ Builder (ICF kit, concrete, labour, preliminaries, programme)	
Nudura ICF package (BuildEase BOQ Builder sheets of this workbook: Summary NET TOTAL)	**£24,103.56**

COMBINED TOTAL - finishes package (incl. additions) + ICF package, excl. VAT	£24,103.56

Pale-yellow cells are the only inputs (rates on each bill sheet, percentages and the ICF hook here). Everything else is a locked formula (protection has no password). Schedules A to D are reference only and are not priced. Named cells: FINISHES_NET_TOTAL, FINISHES_GRAND_TOTAL, ICF_PACKAGE_TOTAL, COMBINED_TOTAL.

IMPORTANT - This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

KEY QUANTITIES (site totals: one dwelling, columns FB / GF / L1 / L2 + roof, net; linked to the bills)		
Timber cladding to the ICF (walls, gables, stack)	**0.00**	m2
Wall linings (ICF faces, partitions, reveals)	**0.00**	m2
Vaulted ceilings on the slope	**259.18**	m2
Internal + cupboard doorsets	**0.00**	nr
Skirting	**0.00**	m
Blockwork partitions (TYPE A / B)	**0.00**	m2
Stud partitions (TYPE C / D)	**0.00**	m2
GF block & beam, both zones (by others)	**0.00**	m2
Roof covering on the slope	**313.95**	m2
Rooflights (TBC)	**6.00**	nr
Openings (opening schedule)	**0.00**	nr

Document control

Issue	Description	Date	By / Status
-	Quotation issue: finishes / ancillary-trades BOQ package for the Nudura ICF quotation (columns FB / GF / L1 / L2 + roof for one single-storey dwelling), merged with the BuildEase BOQ Builder ICF bill + programme. Live pricing workbook: rates blank for pricing by others; ICF_PACKAGE_TOTAL linked to the BOQ Builder NET TOTAL	02/11/2026	BuildEase - T. Smith / For information / pricing by others - NOT FOR CONSTRUCTION

Contents

Finishes Cover (this sheet) - overview
General Notes
Summary of Bills (section breakdown)
Finishes Bill 1 External Claddi
Finishes Bill 2 Internal Lining
Finishes Bill 3 Doors
Finishes Bill 4 Joinery
Finishes Bill 5 Partitions
Finishes Bill 6 Substructure Fl
Finishes Bill 7 Roof
Finishes Bill 8 Openings
Schedule A Areas (not priced)
Schedule B Openings (not priced)
Schedule C Per Level (not priced)
Schedule D Partitions (not priced)

General Notes, Measurement Basis, Assumptions & Exclusions

ES26-063 | Langley Lane Farm, Middleton | Mark Whalley - Ethos Property Development

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

1 Purpose, status, England and building height

ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector. ONE single-storey dwelling on a split-level ground floor (lower zone FFL 124.400 = datum 0: kitchen / dining / snug; upper zone FFL 125.000 = +600), vaulted 35 deg roof: the highest point is the chimney stack top at 6,541 above the lower FFL (ridge ~6,482, geometric) - ~6.7 m above the lowest ground (ground ASSUMED ~150 below each zone FFL - no survey), BELOW 11 m: the 11-18 m fire band does not apply. Approved Document J: the stove flue outlet height (1 m above the roof intersection, rooflights within 2.3 m) is an RFI to the stove installer. Single storey - inside the LABC Warranty 3-storey ICF cap.

1.1

ENGINEER / SPECIALISTS TO DESIGN (floors, steels, roof timbers, oak, partitions and glazing are in the model for coordination only): STRUCTURAL ENGINEER: the indicative steels (UB 203 x 133 ridges / purlins / hip / valley, PFC 180 x 75 eaves beams over the NE set-backs, SHS 100 posts incl. the mullion posts in the lift-and-slide openings, the chimney-stack lintel + trimmers on 2 SHS posts); padstones / pockets in the ICF core (form at the pour); the roof (4 hip / valley heads with no prop in the model; the 16 m wing ridge as a steel); the oak trusses A1-A3; the strip footing (stepped at the zone change); the B&B bearings on the footing course and the step walls.

1.2

This package presents the finishes and ancillary-trade quantities measured by BuildEase alongside the Nudura ICF quotation for Langley Lane Farm, Middleton (ref ES26-063). It is set out as a Bill of Quantities so that the client, their quantity surveyor and trade contractors can price and coordinate the works.

1.3

Status: FOR INFORMATION, COORDINATION AND PRICING BY OTHERS - NOT FOR CONSTRUCTION. Supply and install rates are left blank deliberately - BuildEase / Tremco CPG are not pricing these trades. The Excel workbook is a live pricing document: enter rates and every amount, subtotal and total updates by formula.

1.4

The ICF kit, concrete core, pumping, ICF / floor / roof labour and the build programme are in the BuildEase BOQ Builder sheets of this workbook (Cover / Programme / Summary / A-F). The finishes cover carries a named hook (ICF_PACKAGE_TOTAL) linked to that NET TOTAL.

1.5

PROGRAMME (BOQ Builder sheet 'Programme', 1 ICF crew of 8 + 1 joinery crew of 3, Tom's rule floors / roofs 1 day per plot, pours at 60 m3 / pump-day, 2 days cure): 15 working days = 3 weeks. Sequence: ICF FB d0-0.42; pour d1-2; cure d2-4; GF B&B floor d4-5; ICF L1 d5-7.32; pour d9-10; ICF L2 d10-10.61; pour d11-12; cure d12-14; roof d14-15. ICF concrete 53.33 m3 (geometric, 352 ordered forms: FB 8.35 / L1 35.97 / L2 9.01) in 3 pump days. ALIGNMENT: the proposal prices 4 stillages x 5 weeks hire (GBP 1,600.00); on this programme the alignment is needed from the first ICF lift (FB, day 0) to the last pour (L2, day 12) = 3 weeks on hire - 2 weeks LESS than priced (GBP 640.00 of hire not needed on this programme). The proposal has NOT been changed - confirm the hire period with the client / site team.

1.6

This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price.

1.7

Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

1.8

2 Basis of measurement

Measured generally in accordance with the principles of NRM2 (RICS New Rules of Measurement): work measured net as fixed in position, grouped by work section, units m / m2 / nr / item. NRM2 is referenced for structure only; descriptions are BuildEase's own.

2.1

Quantities are NET. No allowance for waste, laps, cutting or breakage is included unless stated; an "Order guide" with a stated waste % is guidance only.

2.2

Quantity columns: FB (footing courses, both zones), GF (block & beam floor + ground-floor items), L1 (GF walls and everything fixed to them), L2 (gables, chimney stack, vault upstands) and the ROOF. One dwelling: the Site total is the sum of the columns (multiplier 1) and is a live formula.

2.3

Sources: the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; the BuildEase quotation model 03_Models/LF2_build.skp through its spec (04_Logs/specs/LF2_spec.json, LF2_floors.json), the window fit (04_Logs/lf2/lfw_fit.json), the structure dump (roof members, steels, oak trusses, partitions) and the Report Tool component export (04_Logs/takeoff/LF_components.json: inner / outer EPS face areas of the 570 modelled forms, openings net). Measured offline by 05_Scripts/lf_boq.py (no live model).

2.4

3 Assumptions

Walls: footing courses 8in Standard (336.6 overall), GF walls / gables / stack / upstands 6in XR35 (355.6). Frames tight to the back of the outer EPS (101.8): internal reveal ~269, external reveal return ~172.

3.1

Levels: lower FFL 124.400 = 0 (kitchen / dining / snug), upper FFL 125.000 = +600; FB-Lower -689, FB-Upper -231.8; L1 to the underside of the plate 3,341 (plate top 3,385); stack top 6,541; ridge ~6.48 m (geometric, 35 deg planes over the plate line, heel ignored).

3.2

External finish: vertical timber cladding (charred larch or similar) on a ventilated batten zone; feature brickwork / stone provisional; ground ~150 below each zone FFL (not surveyed).

3.3

3.4 Floors: GF precast B&B BY OTHERS in two zones per LF2_floors.json; vaulted ceilings on the slope over the whole internal plan (flat MF ceilings to the stud-walled rooms provisional, not deducted).

3.5 Internal doors: D-01 to D-11 (11) from the plan + 3 provisional cupboard leaves, ironmongery per leaf. Partitions: indicative, from the partition model (blockwork to the vault, studs to 2,537).

3.6 Roof: 35 deg cut roof, member counts / sections from the roof model; hips / ridges / valley from the straight-skeleton height field; 6 rooflights and 8 RWPs counted on the plan crops (TBC).

4 Exclusions (not measured in this package)

4.1 Nudura ICF formwork and accessories (in the Nudura price). ICF wall concrete, pumping, ICF / floor / roof labour and preliminaries are in the BOQ Builder sheets.

4.2 External works, drainage, landscaping, the gabion retaining wall, car parking, boundary fences, the entrance porch (not modelled).

4.3 Floor finishes, decorations, kitchen, sanitaryware, the stove / flue liner, M&E services (heating / UFH, ventilation, electrics) and builder's work.

4.4 Fire-stopping and fire-rated service penetrations, sealants and mastics, except where expressly described.

5 Open items / to be confirmed

5.1 STRUCTURAL ENGINEER: the indicative steels (UB 203 x 133 ridges / purlins / hip / valley, PFC 180 x 75 eaves beams over the NE set-backs, SHS 100 posts incl. the mullion posts in the lift-and-slide openings, the chimney-stack lintel + trimmers on 2 SHS posts); padstones / pockets in the ICF core (form at the pour); the roof (4 hip / valley heads with no prop in the model; the 16 m wing ridge as a steel); the oak trusses A1-A3; the strip footing (stepped at the zone change); the B&B bearings on the footing course and the step walls.

5.2 BEAM SUPPLIER: the lower / upper zone B&B layouts (Bill 6), bearings on the 8in Standard footing course (150 cut off its inside face) and the TYPE A step walls, vents / sleeves through the ICF (form BEFORE the pour).

5.3 ARCHITECT / BUILDING CONTROL (England, Approved Documents): flue height (Approved Document J - RFI to the stove installer: outlet 1 m above the roof intersection, rooflights within 2.3 m); feature brickwork / stone extents; the entrance porch (projects past the roof outline - not modelled); A12 ICF return vs blockwork (RFI); door schedule (privacy sets, cupboards); rooflight count / sizes; Part K guarding at the steps; Part O (large glazing).

5.4 Assumed (not drawn / not modelled): ground ~150 below each zone FFL; cladding build-up (battens + counter-battens on a membrane); the MF ceiling areas; 3 cupboard leaves; 4 privacy sets; 6 rooflights; 8 downpipes; the internal steps; the canopy.

6 What IS in the Nudura price (Quotation ES26-063, NET GBP 24,103.56)

6.1 Nudura ICF kit as modelled in the BuildEase Design Suite: 570 forms modelled (FB 56 / L1 409 / L2 105) / 352 to order after the cut optimiser (FB 44 / L1 244 / L2 64), 8in Standard footing courses + 6in XR35 walls, materials GBP 18,710.85.

6.2 Accessories: VJC clips, end caps, Form-Lock, lintel closures, T-form support straps, spray foam.

6.3 BuildEase Pre-Cut Service GBP 2,624.69; alignment system 4 stillages x 5 weeks hire GBP 1,600.00; haulage GBP 1,168.02 (2 deliveries: FB + L1, then L2; 17 pallets).

6.4 Nothing in Bills 1 to 8 of this finishes package is included in the Nudura price.

7 Pricing instructions to tenderers

7.1 Each bill item has a SUPPLY rate and an INSTALL rate. Insert rates only in the pale-yellow cells of the Excel workbook: Supply = Site total qty x Supply rate; Install = Site total qty x Install rate; Line total = Supply + Install. Items measured as "item" are lump sums: the rate entered is the amount.

7.2 Each bill ends with a Package Summary (section subtotals for Supply / Install / Total and the package total). The Cover carries the full overview: one row per bill, grand totals, optional Preliminaries, Overheads & profit and Contingency percentages (pale-yellow cells; blank = 0) and the ICF package hook.

7.3 All other cells are locked by sheet protection (no password - Review > Unprotect Sheet if a change is genuinely needed) so formulas cannot be overwritten by accident.

7.4 Re-measure and verify all quantities before pricing or ordering. State any qualification against the item in the Notes column.

7.5 The Order guide figures and Schedules A to D are not measured bill items and must not be priced as such. All amounts exclude VAT.

Summary of Bills - section breakdown

ES26-063 | Langley Lane Farm, Middleton | Mark Whalley - Ethos Property Development - amounts by others, excl. VAT

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Bill	Section	Description	Supply £	Install £	Total £
1	1A	Vertical timber cladding to the ICF (NRM2 14 / 16 - package EXT; cladding by others, SPEC TBC)	£0.00	£0.00	£0.00
1	1B	Feature brickwork / stone and coordination (NRM2 14 - package EXT; PROVISIONAL)	£0.00	£0.00	£0.00
Bill 1 - External Wall Cladding to the ICF (vertical timber cladding, plinth, trims, stack			**£0.00**	**£0.00**	**£0.00**
2	2A	Wall linings (NRM2 28 / package DRY)	£0.00	£0.00	£0.00
2	2B	Ceilings (NRM2 28 / package DRY)	£0.00	£0.00	£0.00
2	2C	Jointing, beads and skim (NRM2 28 / package DRY)	£0.00	£0.00	£0.00
Bill 2 - Internal Linings - ICF Faces, Partitions, Vaulted Ceilings, Tape, Beads & Skim			**£0.00**	**£0.00**	**£0.00**
3	3A	Internal doorsets (NRM2 24 / package JOI)	£0.00	£0.00	£0.00
3	3B	Ironmongery - counted PER LEAF (NRM2 24 / package JOI)	£0.00	£0.00	£0.00
Bill 3 - Internal Doors, Cupboard Doors & Ironmongery (per leaf) (package JOI)			**£0.00**	**£0.00**	**£0.00**
4	4A	Skirtings and architraves (NRM2 22 / package JOI)	£0.00	£0.00	£0.00
4	4B	Window boards (NRM2 22 / package JOI)	£0.00	£0.00	£0.00
4	4C	Steps, feature brickwork and sundry joinery (NRM2 22 / 14 - package JOI) - INDICATIVE, not modelled	£0.00	£0.00	£0.00
Bill 4 - Joinery - Skirtings, Architraves, Window Boards, Steps & Sundries (package JOI			**£0.00**	**£0.00**	**£0.00**
5	5A	Blockwork partitions (NRM2 14 - package MAS) - INDICATIVE	£0.00	£0.00	£0.00
5	5B	Timber stud partitions (NRM2 16 - package JOI)	£0.00	£0.00	£0.00
Bill 5 - Internal Partitions - Blockwork TYPE A / B and Timber Studs TYPE C / D (packa			**£0.00**	**£0.00**	**£0.00**
6	6A	Substructure (NRM2 5 / 11 - package GRW; by others - engineer; coordination quantities)	£0.00	£0.00	£0.00
6	6B	GF block & beam - Lower zone (FFL 124.400: kitchen / dining / snug) BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)	£0.00	£0.00	£0.00
6	6C	GF block & beam - Upper zone (FFL 125.000: everything else) BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)	£0.00	£0.00	£0.00
Bill 6 - Substructure and GF Block & Beam Floor, both zones (coordination) (package			**£0.00**	**£0.00**	**£0.00**
7	7A	Roof structure - vaulted cut roof (NRM2 16 - package RFS; roof designer / engineer)	£0.00	£0.00	£0.00
7	7B	Structural steel and oak (NRM2 14 / 16 - package STR; ENGINEER - INDICATIVE, sections not designed)	£0.00	£0.00	£0.00
7	7C	Roof covering, rooflights, eaves and rainwater (NRM2 18 / 33 - package RFC)	£0.00	£0.00	£0.00
7	7D	Roof insulation and VCL (NRM2 18 / 28 - package RFC)	£0.00	£0.00	£0.00
Bill 7 - Roof - Vaulted Cut Roof, Steels, Oak Trusses, Covering, Rooflights, Rainwater &			**£0.00**	**£0.00**	**£0.00**
8	8A	Opening schedule - one line per opening, incl. its accessories (NRM2 25 - package WIN; window / door supplier)	£0.00	£0.00	£0.00
8	8B	Items common to the openings (NRM2 25 - package WIN)	£0.00	£0.00	£0.00
Bill 8 - Opening Schedule - Windows, Glazing Screens & External Doors (one line per			**£0.00**	**£0.00**	**£0.00**
TOTAL - finishes / ancillary trades, net (agrees with the Cover overview)			**£0.00**	**£0.00**	**£0.00**

Schedules A to D are reference schedules and are not priced. Preliminaries, overheads & profit, contingency and the ICF package (BuildEase BOQ Builder) are applied on the Cover.

Bill 1 - External Wall Cladding to the ICF (vertical timber cladding, plinth, trims, stack, feature brick / stone)

Ventilated vertical timber cladding to the ICF EPS faces (GF walls, gables, vault upstands, chimney stack), plinth, trims, reveals and the provisional feature brickwork / stone (systems by others, spec TBC). [NRM2 14 / 16 / package EXT]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB footing	GF floor	L1 GF walls	L2 gables	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	5						Levels: FB = footing courses: one 8in Standard course per floor zone (lower -689, upper -231.8) on the strip footing (by others); GF = GF precast block & beam floor, both zones (by others) + the ground-floor items; L1 = GF walls, 6in XR35, 8 courses to the underside of the plate 3,341; L2 = raked gables W / SE, chimney stack to 6,541, NE vault upstands (6in XR35); RF = vaulted cut roof (35 deg), steels, oak
1A	**Vertical timber cladding to the ICF (NRM2 14 / 16 - package EXT; cladding by others, SPEC TBC)**													
	Elevations (LR Design): vertical timber cladding throughout (charred larch / Shou Sugi Ban or similar - spec TBC), the chimney stack timber clad, feature brickwork / stone where drawn, gabion retaining wall by others. Measured as a ventilated rainscreen on the ICF EPS: breather membrane, 38 x 50 treated battens / counter-battens screwed through the EPS into the ICF webs (vertical boards need horizontal battens on vertical counter-battens), insect mesh top and bottom. Areas = the modelled ICF outer EPS faces (Report Tool component export, openings net): GF walls from each zone FFL up; L2 gables, vault upstands and the chimney stack. Ground ASSUMED ~150 below each zone FFL - the band below FFL is a plinth (1A.4). No fire-band requirement (single storey, < 11 m).													
1A.1	Vertical timber cladding (charred larch or similar, spec TBC) on 38 x 50 battens + counter-battens and a vapour-permeable breather membrane on the ICF EPS face, fixings into the ICF webs - GF walls, gables and vault upstands, net of openings	m2			174.24	21.47		**195.71**			£0.00	£0.00	**£0.00**	Order guide +15% = 225.1
1A.2	Chimney stack (ICF box over the flue, to 6,541): timber cladding as 1A.1 incl. the stack head / capping and flashings interface (Bill 7)	m2				10.49		**10.49**			£0.00	£0.00	**£0.00**	Order guide +15% = 12.1; stack faces outside the building line
1A.3	External corner trims / boarded corners (90 deg corners + the stack corners)	m			23.39	12.80		**36.19**			£0.00	£0.00	**£0.00**	Order guide +10% = 39.8; 7 nr 90 deg + 4 stack corners
1A.4	External corner trims to the obtuse (125 / 145 deg) corners of the wing and the NE set-backs	m			26.73			**26.73**			£0.00	£0.00	**£0.00**	Order guide +10% = 29.4; 8 nr
1A.5	Plinth to the exposed ICF below the cladding, ground (~-150) to each zone FFL: dark plinth render / board on the EPS (ICF-compatible, spec TBC)	m2			11.31			**11.31**			£0.00	£0.00	**£0.00**	Perimeter 82.8 m x ~150 band
1A.6	Base of the cladding: insect mesh / ventilation closer, starter batten and drip at the plinth line	m			50.54			**50.54**			£0.00	£0.00	**£0.00**	Order guide +10% = 55.6; floor-length screens / doors deducted (32.3 m)
1A.7	Reveal linings to the openings (head + jambs), girth ~172 (outer EPS + cladding zone): boarded / aluminium reveal trims to suit the RAL 7016 frames	m2			21.81			**21.81**			£0.00	£0.00	**£0.00**	Order guide +10% = 24.0; 21 openings
1A.8	Movement / sealant joint and closers between the cladding / reveal linings and the window and door frames	m			126.93			**126.93**			£0.00	£0.00	**£0.00**	Order guide +10% = 139.6
1A.9	Sills / thresholds: aluminium sills to the windows, threshold drips at the screens and doors (to the frame supplier's detail)	m			35.01			**35.01**			£0.00	£0.00	**£0.00**	21 openings (spec widths)
1A.10	Head of the cladding: ventilation gap / mesh under the soffits (eaves) and the verge interface at the gables	m			60.54	21.02		**81.57**			£0.00	£0.00	**£0.00**	Order guide +10% = 89.7
1B	**Feature brickwork / stone and coordination (NRM2 14 - package EXT; PROVISIONAL)**													
	Feature brickwork / stone is noted on the elevations but not dimensioned - an allowance for a brick-slip / stone-slip panel system on the ICF (adhesive / mechanically fixed) is carried until the architect confirms extents. The fair-faced feature brickwork to the fireplace (inside, plan note) is in Bill 4.													
1B.1	Feature brickwork / stone panels on the ICF (slips on a carrier system, spec and extent TBC - architect)	item									£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. PROVISIONAL
1B.2	Rainwater pipe brackets / fixings through the cladding into the ICF webs (positions per the drainage design)	item									£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Bill 7C downpipes
1B.3	External light / socket / vent penetrations through the cladding and the ICF (sleeves set BEFORE the pours)	item									£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. M&E coordination

PACKAGE SUMMARY - Bill 1 External Wall Cladding to the ICF (vertical timber cladding, plinth, trims, stack, feature brick / stone) (package EXT; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
1A	Vertical timber cladding to the ICF (NRM2 14 / 16 - package EXT; cladding by others, SPEC TBC)	£0.00	£0.00	**£0.00**
1B	Feature brickwork / stone and coordination (NRM2 14 - package EXT; PROVISIONAL)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 1, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 2 - Internal Linings - ICF Faces, Partitions, Vaulted Ceilings, Tape, Beads & Skim

Dry linings to the ICF inner faces (thermal barrier to the EPS), plaster / board to the partitions, reveals, the vaulted ceilings on the slope and the provisional MF ceilings. [NRM2 28 / package DRY]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB footing	GF floor	L1 GF walls	L2 gables	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		**1**	**1**	**1**	**1**	**1**	**5**						Levels: FB = footing courses: one 8in Standard course per floor zone (lower -689, upper -231.8) on the strip footing (by others); GF = GF precast block & beam floor, both zones (by others) + the ground-floor items; L1 = GF walls, 6in XR35, 8 courses to the underside of the plate 3,341; L2 = raked gables W / SE, chimney stack to 6,541, NE vault upstands (6in XR35); RF = vaulted cut roof (35 deg), steels, oak
2A	**Wall linings (NRM2 28 / package DRY)**													
	ICF inner faces from the component export (openings net) from each zone FFL to the plate (3,341), the L2 gable / upstand inner faces in the vault and the chimney-stack face inside the building. EPS faces must be covered by a thermal barrier (min. 12.5 mm board, mechanically fixed to the ICF webs) whatever the finish. Blockwork partitions (TYPE A / B, to the rafter underside) plastered both faces; stud partitions (TYPE C / D, to the 2,537 ceiling) boarded both faces - areas from the partition model (INDICATIVE, door gaps as modelled).													
2A.1	GF ICF external-wall inner faces: 12.5 mm wallboard on dabs + mechanical fixings to the ICF webs (MR board in the wet rooms), thermal barrier to the EPS	m2			148.13			**148.13**			£0.00	£0.00	**£0.00**	Order guide +10% = 162.9
2A.2	Gable, vault-upstand and chimney-stack ICF inner faces in the vaulted rooms: 12.5 mm board mechanically fixed (thermal barrier)	m2				39.96		**39.96**			£0.00	£0.00	**£0.00**	Order guide +10% = 44.0; stack face 17.5 m2
2A.3	Blockwork partitions TYPE A / B - both faces: 2-coat plaster / or dabbed board + skim to the rafter underside	m2			467.28			**467.28**			£0.00	£0.00	**£0.00**	Order guide +10% = 514.0; A 211.9 + B 21.8 m2 one face
2A.4	Stud partitions TYPE C / D - both faces: 12.5 mm board (MR / moisture board in the bathrooms / WC)	m2			56.66			**56.66**			£0.00	£0.00	**£0.00**	Order guide +10% = 62.3; C 21.6 + D 6.7 m2 one face
2A.5	Internal reveals to the openings in the ICF, jambs and heads, 269 deep: board / bonding + skim	m2			34.12			**34.12**			£0.00	£0.00	**£0.00**	Order guide +10% = 37.5
2B	**Ceilings (NRM2 28 / package DRY)**													
	VAULTED rooms: plasterboard to the rafter underside (warm roof - insulation in Bill 7D), measured ON THE SLOPE over the internal plan inside the ICF (212.3 m2 x 1.221) - gross, the flat-ceilinged rooms NOT deducted. Section C-C: the stud-walled rooms (WC, bathrooms, cloaks, store) have a MF suspended ceiling at 2,537 above their FFL (areas not on the drawings - PROVISIONAL).													
2B.1	Vaulted ceilings: 12.5 mm plasterboard (or insulated plasterboard as the SAP) on the rafter / batten soffits, on the 35 deg slope incl. the oak truss and steel interfaces	m2					259.18	**259.18**			£0.00	£0.00	**£0.00**	Order guide +10% = 285.1
2B.2	MF suspended ceiling at 2,537 to the stud-walled rooms (WC, bathrooms, cloaks, store) incl. 12.5 board - area TBC	item									£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. PROVISIONAL - section C-C
2B.3	Boxing / plasterboard casings to the exposed steels where not left exposed (UB ridges / purlins) - finish TBC	item									£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Architect
2C	**Jointing, beads and skim (NRM2 28 / package DRY)**													
2C.1	Scrim tape, board joints (walls / 1.2 m; ceilings / 1.2 + 2.4 m)	m			556.36			**556.36**			£0.00	£0.00	**£0.00**	Order guide +10% = 612.0
2C.2	Scrim tape / angle bead, wall to ceiling angles (ICF inner perimeter + partition heads both sides)	m			202.29			**202.29**			£0.00	£0.00	**£0.00**	Estimate; Order guide +10% = 222.5
2C.3	Angle bead, window / door reveals	m			126.93			**126.93**			£0.00	£0.00	**£0.00**	Order guide +10% = 139.6
2C.4	Skim coat, 2-3 mm, to all net wall, reveal and ceiling faces (board and plastered blockwork)	m2			706.19	39.96	259.18	**1,005.33**			£0.00	£0.00	**£0.00**	Face layer only
2D	**Ordering guide (not a measured item)**													
2D.1	*Plasterboard to purchase, all types, before waste*	*m2*			*238.91*	*39.96*	*259.18*	*538.05*					*not priced*	*Guide only (+10% waste)*

PACKAGE SUMMARY - Bill 2 Internal Linings - ICF Faces, Partitions, Vaulted Ceilings, Tape, Beads & Skim (package DRY; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
2A	Wall linings (NRM2 28 / package DRY)	£0.00	£0.00	**£0.00**
2B	Ceilings (NRM2 28 / package DRY)	£0.00	£0.00	**£0.00**
2C	Jointing, beads and skim (NRM2 28 / package DRY)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 2, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 3 - Internal Doors, Cupboard Doors & Ironmongery (per leaf)

Internal doorsets D-01 to D-11 and provisional cupboard doors with ironmongery counted per leaf (14 leaves). [NRM2 24 / package JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB footing	GF floor	L1 GF walls	L2 gables	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		**1**	**1**	**1**	**1**	**1**	**5**						Levels: FB = footing courses: one 8in Standard course per floor zone (lower -689, upper -231.8) on the strip footing (by others); GF = GF precast block & beam floor, both zones (by others) + the ground-floor items; L1 = GF walls, 6in XR35, 8 courses to the underside of the plate 3,341; L2 = raked gables W / SE, chimney stack to 6,541, NE vault upstands (6in XR35); RF = vaulted cut roof (35 deg), steels, oak
3A	**Internal doorsets (NRM2 24 / package JOI)**													
	Doors D-01 to D-11 from the LR Design plan (11 internal doors, openings ~910 as dimensioned) -> 838 x 1,981 leaves in 32 x 140 / 115 lining sets to suit the 140 / 100 blockwork and the stud walls. No internal double doors are drawn (no flush bolts). Cupboard doors to the store, cloaks and pantry are NOT drawn as doors - 3 leaves PROVISIONAL. Single dwelling: no fire doors required by ADB vol 1 for a single-storey house (escape windows / inner-room rules - architect).													
3A.1	Internal doorset, 838 x 1,981 leaf (spec TBC), lining set, stops, to blockwork / stud openings ~910	nr			11.00			**11.00**			£0.00	£0.00	**£0.00**	D-01, D-02, D-03, D-04, D-05, D-06, D-07, D-08, D-09, D-10, D-11
3A.2	Cupboard / store doorset, 1 leaf (size TBC), lining set, stops - store, cloaks, pantry	nr			3.00			**3.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - store (C1), cloaks (C3), pantry (A3)
3B	**Ironmongery - counted PER LEAF (NRM2 24 / package JOI)**													
3B.1	Butt hinges, 100 mm, pairs (1.5 pair per leaf)	pr			16.50			**16.50**			£0.00	£0.00	**£0.00**	1.5 pr per door leaf
3B.2	Standard sets: tubular latch, lever pair on roses	set			7.00			**7.00**			£0.00	£0.00	**£0.00**	Internal doors less the privacy sets
3B.3	Bathroom / WC / en-suite sets: privacy lock, thumb-turn with emergency release, lever pair	set			4.00			**4.00**			£0.00	£0.00	**£0.00**	ASSUMED 4 (WC, bathroom, 2 en-suites) - adjust to the door schedule
3B.4	Door stops, floor or skirting mounted	nr			11.00			**11.00**			£0.00	£0.00	**£0.00**	One per leaf
3B.5	Cupboard ironmongery PER LEAF: 1.5 pr hinges (as pairs)	pr			4.50			**4.50**			£0.00	£0.00	**£0.00**	Per cupboard leaf
3B.6	Cupboard ironmongery PER LEAF: knob / pull handle + magnetic or roller catch	set			3.00			**3.00**			£0.00	£0.00	**£0.00**	Per cupboard leaf

Flush bolts: one per double (pair) leaf door - none drawn internally. External doors and their ironmongery are in Bill 8 (opening schedule).

PACKAGE SUMMARY - Bill 3 Internal Doors, Cupboard Doors & Ironmongery (per leaf) (package JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
3A	Internal doorsets (NRM2 24 / package JOI)	£0.00	£0.00	**£0.00**
3B	Ironmongery - counted PER LEAF (NRM2 24 / package JOI)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 3, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 4 - Joinery - Skirtings, Architraves, Window Boards, Steps & Sundries

Second-fix joinery measured from the model wall faces and the spec openings; the internal steps, the fireplace brickwork and the sundries indicative. [NRM2 22 / package JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB footing	GF floor	L1 GF walls	L2 gables	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	5						Levels: FB = footing courses: one 8in Standard course per floor zone (lower -689, upper -231.8) on the strip footing (by others); GF = GF precast block & beam floor, both zones (by others) + the ground-floor items; L1 = GF walls, 6in XR35, 8 courses to the underside of the plate 3,341; L2 = raked gables W / SE, chimney stack to 6,541, NE vault upstands (6in XR35); RF = vaulted cut roof (35 deg), steels, oak
4A	**Skirtings and architraves (NRM2 22 / package JOI)**													
	No room model: skirting = the ICF inner perimeter less the floor-length screens / doors + the partitions both faces less the door openings. Architraves: per face 2 legs x 2150 + (opening + 2 x 70), internal and cupboard doors both faces, the external doors / screens have plastered reveals (no architrave).													
4A.1	Skirting 18 x 119 MDF / timber, primed, fixed to the linings / plugged to the blockwork	m			145.81			**145.81**			£0.00	£0.00	**£0.00**	Order guide +10% = 160.4
4A.2	Architrave 18 x 69 to internal and cupboard doors, both faces	m			149.80			**149.80**			£0.00	£0.00	**£0.00**	Order guide +10% = 164.8
4B	**Window boards (NRM2 22 / package JOI)**													
	The 3 windows with a sill (1,060 high casements; the 13 glazing screens and the doors are floor-length - no board): board = opening + 2 x 50, depth 269 + 25.													
4B.1	Window board MDF / oak 294 x 785 long	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	L1-DW-11x (685 wide, sill 1,048 above its FFL)
4B.2	Window board MDF / oak 294 x 1,010 long	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	L1-DW-03 (910 wide, sill 1,048 above its FFL)
4B.3	Window board MDF / oak 294 x 1,260 long	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	L1-DW-02 (1,160 wide, sill 1,048 above its FFL)
4C	**Steps, feature brickwork and sundry joinery (NRM2 22 / 14 - package JOI) - INDICATIVE, not modelled**													
	The upper zone (FFL 125.000) is 600 above the lower zone (124.400): the plan shows 4 steps between them (hall / link).													
4C.1	Internal steps between the floor zones (600 rise, 4 steps as drawn): treads / nosings / risers on the screed step, incl. handrail where required (Part K)	item		1.00				**1.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - plan
4C.2	Fair-faced feature brickwork to the fireplace / chimney breast (internal, plan note), incl. hearth (Approved Document J)	item			1.00			**1.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - stove installer / architect
4C.3	Boxings to services / SVPs (plan: SVPs at the WC, bathrooms, en-suites, utility) and pipe runs	item									£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Allowance - M&E design
4C.4	Oak truss / exposed steel finishing: sanding, oiling / painting of the exposed members in the vaulted rooms	item									£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Finish TBC

PACKAGE SUMMARY - Bill 4 Joinery - Skirtings, Architraves, Window Boards, Steps & Sundries (package JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
4A	Skirtings and architraves (NRM2 22 / package JOI)	£0.00	£0.00	**£0.00**
4B	Window boards (NRM2 22 / package JOI)	£0.00	£0.00	**£0.00**
4C	Steps, feature brickwork and sundry joinery (NRM2 22 / 14 - package JOI) - INDICATIVE, not modelled	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 4, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 5 - Internal Partitions - Blockwork TYPE A / B and Timber Studs TYPE C / D

Indicative internal partitions from the partition model: blockwork 49.8 m (to the vault), studs 11.2 m (to the 2,537 ceiling). Linings in Bill 2, doors in Bill 3. [NRM2 14 / 16 / package MAS / JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB footing	GF floor	L1 GF walls	L2 gables	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	5						Levels: FB = footing courses: one 8in Standard course per floor zone (lower -689, upper -231.8) on the strip footing (by others); GF = GF precast block & beam floor, both zones (by others) + the ground-floor items; L1 = GF walls, 6in XR35, 8 courses to the underside of the plate 3,341; L2 = raked gables W / SE, chimney stack to 6,541, NE vault upstands (6in XR35); RF = vaulted cut roof (35 deg), steels, oak
5A	**Blockwork partitions (NRM2 14 - package MAS) - INDICATIVE**													
	Traced from the LR Design buildability plan into the model (lf2_partitions.rb; struct_dump "LF Partitions"): TYPE A 140 / TYPE B 100 dense blockwork standing on the zone's B&B top (the step walls from the LOWER B&B top) and rising to the VAULT (rafter underside - raked heads), door gaps as modelled. Areas = elevation area of each run (raked top). A12 (by the link) may be an ICF return - RFI. Load-bearing blockwork on the B&B needs the beam supplier / engineer to confirm (double beams / bearings).													
5A.1	TYPE A 140 blockwork - A1 kitchen / utility (3.65 m, raked head to 6,068)	m2			18.33			**18.33**			£0.00	£0.00	**£0.00**	z -232 to 6,068
5A.2	TYPE A 140 blockwork - A2 kitchen / lounge + hall (6.26 m, raked head to 6,068)	m2			38.01			**38.01**			£0.00	£0.00	**£0.00**	z -232 to 6,068
5A.3	TYPE A 140 blockwork - A3 kitchen / pantry (3.04 m, raked head to 5,638)	m2			14.59			**14.59**			£0.00	£0.00	**£0.00**	z -232 to 5,638
5A.4	TYPE A 140 blockwork - A4 hall / WC (3.58 m, raked head to 5,607)	m2			16.22			**16.22**			£0.00	£0.00	**£0.00**	z 375 to 5,607
5A.5	TYPE A 140 blockwork - A5 link west (1.94 m, raked head to 5,916)	m2			9.43			**9.43**			£0.00	£0.00	**£0.00**	z 375 to 5,916
5A.6	TYPE A 140 blockwork - A6 corridor (7.39 m, raked head to 4,557)	m2			30.50			**30.50**			£0.00	£0.00	**£0.00**	z 375 to 4,557
5A.7	TYPE A 140 blockwork - A7 sleeper / link (2.95 m, raked head to 5,797)	m2			14.56			**14.56**			£0.00	£0.00	**£0.00**	z 375 to 5,797
5A.8	TYPE A 140 blockwork - A8 bed 1 west (4.88 m, raked head to 5,842)	m2			22.65			**22.65**			£0.00	£0.00	**£0.00**	z 375 to 5,842
5A.9	TYPE A 140 blockwork - A9 wing corridor (3.42 m, raked head to 4,866)	m2			14.58			**14.58**			£0.00	£0.00	**£0.00**	z 375 to 4,866
5A.10	TYPE A 140 blockwork - A10 ensuite (3.86 m, raked head to 5,809)	m2			17.94			**17.94**			£0.00	£0.00	**£0.00**	z 375 to 5,809
5A.11	TYPE A 140 blockwork - A11 ensuite south (2.53 m, raked head to 4,432)	m2			10.27			**10.27**			£0.00	£0.00	**£0.00**	z 375 to 4,432
5A.12	TYPE A 140 blockwork - A12 ICF return? (RFI) (1.18 m, raked head to 4,805)	m2			4.81			**4.81**			£0.00	£0.00	**£0.00**	z 375 to 4,805
5A.13	TYPE B 100 blockwork - B1 utility (2.54 m, raked head to 6,019)	m2			12.07			**12.07**			£0.00	£0.00	**£0.00**	z 375 to 6,019
5A.14	TYPE B 100 blockwork - B2 utility (1.56 m, raked head to 4,242)	m2			6.04			**6.04**			£0.00	£0.00	**£0.00**	z 375 to 4,242
5A.15	TYPE B 100 blockwork - B3 utility (1.04 m, raked head to 4,242)	m2			3.65			**3.65**			£0.00	£0.00	**£0.00**	z 375 to 4,242
5A.16	Wall ties / starters to the ICF (resin or tie strips into the ICF core / webs) at the partition abutments, every 225 vertically	nr			339.00			**339.00**			£0.00	£0.00	**£0.00**	Estimate: one abutment per run
5B	**Timber stud partitions (NRM2 16 - package JOI)**													
	TYPE C 70 studs (100 overall with board) and TYPE D 146 studs, on the screed up to the 2,537 suspended ceiling (section C-C), C16 studs at 600 c/c, head and sole plates, one noggin row; acoustic quilt (Part E E2 internal walls round bedrooms / WCs).													
5B.1	TYPE C 38 x 70 C16 stud partition - C1 store (0.66 m x 2,537)	m2			1.67			**1.67**			£0.00	£0.00	**£0.00**	
5B.2	TYPE C 38 x 70 C16 stud partition - C2 WC (2.20 m x 2,537)	m2			5.57			**5.57**			£0.00	£0.00	**£0.00**	
5B.3	TYPE C 38 x 70 C16 stud partition - C3 cloaks (0.66 m x 2,537)	m2			1.69			**1.69**			£0.00	£0.00	**£0.00**	
5B.4	TYPE C 38 x 70 C16 stud partition - C4 bath (2.88 m x 2,537)	m2			7.32			**7.32**			£0.00	£0.00	**£0.00**	
5B.5	TYPE C 38 x 70 C16 stud partition - C5 bath (2.13 m x 2,537)	m2			5.40			**5.40**			£0.00	£0.00	**£0.00**	
5B.6	TYPE D 38 x 146 C16 stud partition - D1 link (2.64 m x 2,537)	m2			6.69			**6.69**			£0.00	£0.00	**£0.00**	

Ref	Description	Unit	FB footing	GF floor	L1 GF walls	L2 gables	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	5						Levels: FB = footing courses: one 8in Standard course per floor zone (lower -689, upper -231.8) on the strip footing (by others); GF = GF precast block & beam floor, both zones (by others) + the ground-floor items; L1 = GF walls, 6in XR35, 8 courses to the underside of the plate 3,341; L2 = raked gables W / SE, chimney stack to 6,541, NE vault upstands (6in XR35); RF = vaulted cut roof (35 deg), steels, oak
5B.7	38 x 70 / 38 x 146 C16 studs, head + sole plates, noggins - timber estimate (supply)	m			104.54			**104.54**			£0.00	£0.00	**£0.00**	Studs @ 600 + 3 x run length - ordering estimate
5B.8	Acoustic mineral wool quilt (25 mm, min 10 kg/m3) in the stud voids	m2			28.33			**28.33**			£0.00	£0.00	**£0.00**	
5B.9	Ply pattresses for sanitaryware / wall-hung fittings in the stud walls (wet rooms)	item									£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Allowance

PACKAGE SUMMARY - Bill 5 Internal Partitions - Blockwork TYPE A / B and Timber Studs TYPE C / D (package MAS / JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
5A	Blockwork partitions (NRM2 14 - package MAS) - INDICATIVE	£0.00	£0.00	**£0.00**
5B	Timber stud partitions (NRM2 16 - package JOI)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 5, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 6 - Substructure and GF Block & Beam Floor, both zones (coordination)

Coordination quantities for the engineer / groundworker / beam supplier: strip footing, protection, sleeper wall, vents and the GF block & beam in the lower and upper zones. [NRM2 5 / 11 / 14 / package GRW / FLR]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB footing	GF floor	L1 GF walls	L2 gables	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		**1**	**1**	**1**	**1**	**1**	**5**						Levels: FB = footing courses: one 8in Standard course per floor zone (lower -689, upper -231.8) on the strip footing (by others); GF = GF precast block & beam floor, both zones (by others) + the ground-floor items; L1 = GF walls, 6in XR35, 8 courses to the underside of the plate 3,341; L2 = raked gables W / SE, chimney stack to 6,541, NE vault upstands (6in XR35); RF = vaulted cut roof (35 deg), steels,
6A	**Substructure (NRM2 5 / 11 - package GRW; by others - engineer; coordination quantities)**													
	The ICF FB (one 8in Standard course in each floor zone: lower -689 to -231.8, upper -231.8 to 225.4) stands on a concrete strip footing BY OTHERS (size by the engineer - not modelled). The GF block & beam bears on the footing course (150 cut off its INSIDE face at the bearing) over a ventilated void: vents / sleeves through the ICF must be FORMED BEFORE THE POUR. NOT in the Nudura price.													
6A.1	Strip footing under the ICF FB (concrete, width / depth / reinforcement by the engineer), stepped at the zone change, incl. starter bars into the ICF core	m	81.61					**81.61**			£0.00	£0.00	**£0.00**	FB centre-line length - PROVISIONAL, engineer
6A.2	Protection board / DPM to the below-ground ICF EPS faces before backfill (ICF-compatible, solvent-free)	m2	39.69		13.98			**53.67**			£0.00	£0.00	**£0.00**	Order guide +15% = 61.7
6A.3	Perimeter land drain at footing level (perforated pipe in clean stone, geotextile) - IF required by the site investigation	m	82.80					**82.80**			£0.00	£0.00	**£0.00**	PROVISIONAL
6A.4	Blockwork sleeper wall S1 under the lower-zone B&B (140 blockwork on its footing) - by the groundworker / engineer	m	6.20					**6.20**			£0.00	£0.00	**£0.00**	S1 sleeper wall (under B&B)
6A.5	Telescopic underfloor vents / sleeves through the ICF to the B&B void (~2 m c/c) - set BEFORE the FB / L1 pour	nr	42.00					**42.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - perimeter / 2 m
6A.6	Gabion retaining wall (elevations, by others) and the external level change between the zones	item									£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. External works - by others
6B	**GF block & beam - Lower zone (FFL 124.400: kitchen / dining / snug) BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)**													
	As modelled (LF2_floors.json): 150 precast B&B (67.35 m2 at the bearing) + 150 insulation + 82 screed (63.21 m2 inside the ICF), top of screed = FFL 0. Indicative - the beam supplier designs the layout.													
6B.1	Precast prestressed beam & infill block floor (150), brushed-in grout, bearing on the footing course	m2		67.35				**67.35**			£0.00	£0.00	**£0.00**	
6B.2	DPM / ground-gas membrane over the B&B, lapped and sealed to the ICF (per the site investigation)	m2		63.21				**63.21**			£0.00	£0.00	**£0.00**	
6B.3	150 rigid PIR / EPS floor insulation	m2		63.21				**63.21**			£0.00	£0.00	**£0.00**	
6B.4	Separating layer + 82 sand / cement or flowing screed (top = FFL), UFH pipework by the M&E	m2		63.21				**63.21**			£0.00	£0.00	**£0.00**	
6C	**GF block & beam - Upper zone (FFL 125.000: everything else) BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)**													
	As modelled (LF2_floors.json): 150 precast B&B (158.63 m2 at the bearing) + 150 insulation + 75 screed (149.10 m2 inside the ICF), top of screed = FFL 600. Indicative - the beam supplier designs the layout.													
6C.1	Precast prestressed beam & infill block floor (150), brushed-in grout, bearing on the footing course	m2		158.63				**158.63**			£0.00	£0.00	**£0.00**	
6C.2	DPM / ground-gas membrane over the B&B, lapped and sealed to the ICF (per the site investigation)	m2		149.10				**149.10**			£0.00	£0.00	**£0.00**	
6C.3	150 rigid PIR / EPS floor insulation	m2		149.10				**149.10**			£0.00	£0.00	**£0.00**	
6C.4	Separating layer + 75 sand / cement or flowing screed (top = FFL), UFH pipework by the M&E	m2		149.10				**149.10**			£0.00	£0.00	**£0.00**	
6C.5	25 PIR perimeter edge insulation upstand to the screed against the ICF (inner perimeter x 0.25)	m2		20.08				**20.08**			£0.00	£0.00	**£0.00**	
6C.6	Step between the zones (600): the B&B bearing on the TYPE A step walls (A1 / A2 / A3) - beam supplier / engineer	item		1.00				**1.00**			£0.00	£0.00	**£0.00**	Coordination

PACKAGE SUMMARY - Bill 6 Substructure and GF Block & Beam Floor, both zones (coordination) (package GRW / FLR; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
6A	Substructure (NRM2 5 / 11 - package GRW; by others - engineer; coordination quantities)	£0.00	£0.00	**£0.00**
6B	GF block & beam - Lower zone (FFL 124.400: kitchen / dining / snug) BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)	£0.00	£0.00	**£0.00**
6C	GF block & beam - Upper zone (FFL 125.000: everything else) BY OTHERS (NRM2 14 / 16 - package FLR; beam supplier design)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 6, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 7 - Roof - Vaulted Cut Roof, Steels, Oak Trusses, Covering, Rooflights, Rainwater & Insulation

Vaulted 35 deg cut roof (C24 on UB ridges / purlins), indicative steels and oak trusses A1-A3, slate / tile covering, rooflights, eaves, rainwater, the stack flashings and the warm-roof insulation. [NRM2 14 / 16 / 18 / package RFS / STR / RFC]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB footing	GF floor	L1 GF walls	L2 gables	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	5						Levels: FB = footing courses: one 8in Standard course per floor zone (lower -689, upper -231.8) on the strip footing (by others); GF = GF precast block & beam floor, both zones (by others) + the ground-floor items; L1 = GF walls, 6in XR35, 8 courses to the underside of the plate 3,341; L2 = raked gables W / SE, chimney stack to 6,541, NE vault upstands (6in XR35); RF = vaulted cut roof (35 deg), steels, oak trusses, covering, rainwater
7A	**Roof structure - vaulted cut roof (NRM2 16 - package RFS; roof designer / engineer)**													
	Cut roof at 35 deg on the spec roof outline (gables W and SE, 250 overhang at the eaves; the NE walls are set back from the straight eaves line on PFC eaves beams): plate top 3,385, ridge ~6.48 m above the lower FFL (geometric). Members from the BuildEase roof model (struct_dump "Roof structure - LF Main roof", 163 members, sections as framed - roof designer to confirm): rafters bear on UB ridges / purlins (vaulted - no ceiling ties). ENGINEER: 4 hip / valley ends are reported "no prop / girder under it"; the 16 m wing ridge is a steel (FormFramer could not size it).													
7A.1	Jack rafters (hip) 47 x 245 C24	nr					91.00	**91.00**			£0.00	£0.00	**£0.00**	428.1 m total length (model)
7A.2	Common rafters 47 x 245 C24	nr					56.00	**56.00**			£0.00	£0.00	**£0.00**	319.4 m total length (model)
7A.3	Cripple rafters 47 x 245 C24	nr					6.00	**6.00**			£0.00	£0.00	**£0.00**	18.4 m total length (model)
7A.4	Trimmers at the chimney stack 47 x 245 C24	nr					4.00	**4.00**			£0.00	£0.00	**£0.00**	4.3 m total length (model)
7A.5	Crown rafter 47 x 245 C24	nr					1.00	**1.00**			£0.00	£0.00	**£0.00**	5.7 m total length (model)
7A.6	Hip rafters 100 x 320 GL24h	nr					1.00	**1.00**			£0.00	£0.00	**£0.00**	2.5 m total length (model)
7A.7	Hip rafters 47 x 295 C24	nr					1.00	**1.00**			£0.00	£0.00	**£0.00**	5.9 m total length (model)
7A.8	Ridge board 47 x 295 C16	nr					1.00	**1.00**			£0.00	£0.00	**£0.00**	11.3 m total length (model)
7A.9	Trimming rafter (2nd ply) at the stack 47 x 245 C24	nr					1.00	**1.00**			£0.00	£0.00	**£0.00**	5.8 m total length (model)
7A.10	Valley rafter 47 x 295 C24	nr					1.00	**1.00**			£0.00	£0.00	**£0.00**	5.0 m total length (model)
7A.11	*Roof timber - total length of the above members (ordering guide)*	*m*					*806.46*	*806.46*					*not priced*	*Order guide +10% = 887.1*
7A.12	Wall plate (47 x 100, 44 bed) on the ICF eaves walls, bedded and anchored to the ICF core	m			60.54			**60.54**			£0.00	£0.00	**£0.00**	Order guide +10% = 66.6; eaves wall line (incl. the PFC set-back beams)
7A.13	Holding-down straps / anchors, wall plate to the ICF at max 2.0 m c/c + at the corners	nr			39.00			**39.00**			£0.00	£0.00	**£0.00**	
7A.14	Rafter clips / connectors (model: rafter-to-plate / ridge / hip clips)	nr					150.00	**150.00**			£0.00	£0.00	**£0.00**	struct_dump TCP clips
7A.15	Gable ladders / verge framing at the W and SE gables (on the raked ICF gables)	m					21.02	**21.02**			£0.00	£0.00	**£0.00**	2 rakes
7B	**Structural steel and oak (NRM2 14 / 16 - package STR; ENGINEER - INDICATIVE, sections not designed)**													
	Indicative steels in the model ("LF Steels"): UB 203 x 133 ridges / purlins / hip / valley carrying the vaulted rafters, PFC 180 x 75 eaves beams over the NE set-backs, SHS 100 posts, the chimney-stack lintel + trimmers (inside face) on 2 SHS posts, mullion posts in the large glazed openings. Lengths from the model (principal axis); sections, connections, bearings / padstones in the ICF core (formed at the pour) and finishes by the engineer. Oak arched trusses A1-A3 (one smooth arch under the rafters) by the oak framer.													
7B.1	PFC 180x75 - eaves beam over setback	m					2.41	**2.41**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.2	PFC 180x75 - eaves beam over setback	m					2.82	**2.82**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.3	PFC 180x75 - eaves beam over setback	m					5.43	**5.43**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.4	SHS 100 - GC-24 (P8)	m					2.61	**2.61**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.5	SHS 100 - GC-24 (P11)	m					2.61	**2.61**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.6	SHS 100 - GC-24 (P14)	m					2.61	**2.61**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.7	SHS 100 - GC-24 (P15)	m					2.61	**2.61**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.8	SHS 100 - GC-24A	m					2.61	**2.61**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.9	SHS 100 - stack post S (indicative)	m					3.14	**3.14**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.10	SHS 100 - stack post N (indicative)	m					3.14	**3.14**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.11	SHS 100 - GC-23 (DW-06 mullion)	m					2.41	**2.41**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.12	SHS 100 - GC-23 (DW-07 mullion)	m					2.41	**2.41**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.13	SHS 100 - GC-23 (DW-04/05 mullion)	m					2.41	**2.41**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.14	UB 203x133 - Ridge-01/02 (north block)	m					11.07	**11.07**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.15	UB 203x133 - Ridge-05 (hip to NE corner)	m					5.13	**5.13**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.16	UB 203x133 - Hip (north block / wing)	m					2.49	**2.49**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.17	UB 203x133 - Valley-04	m					4.20	**4.20**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.18	UB 203x133 - Ridge-06 (wing)	m					15.94	**15.94**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.19	UB 203x133 - Purlin-01a/02a	m					11.12	**11.12**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.20	UB 203x133 - Purlin-01b/02b	m					12.88	**12.88**			£0.00	£0.00	**£0.00**	Model length - engineer

Ref	Description	Unit	FB footing	GF floor	L1 GF walls	L2 gables	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	5						Levels: FB = footing courses: one 8in Standard course per floor zone (lower -689, upper -231.8) on the strip footing (by others); GF = GF precast block & beam floor, both zones (by others) + the ground-floor items; L1 = GF walls, 6in XR35, 8 courses to the underside of the plate 3,341; L2 = raked gables W / SE, chimney stack to 6,541, NE vault upstands (6in XR35); RF = vaulted cut roof (35 deg), steels, oak
7B.21	UB 203x133 - Purlin-06a (wing NE)	m					19.07	**19.07**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.22	UB 203x133 - Purlin-06b (wing SW)	m					15.36	**15.36**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.23	UB 203x133 - stack lintel (inside face)	m					2.02	**2.02**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.24	UB 203x133 - stack trimmer S	m					0.84	**0.84**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.25	UB 203x133 - stack trimmer N	m					0.84	**0.84**			£0.00	£0.00	**£0.00**	Model length - engineer
7B.26	Padstones / bearing plates / pockets in the ICF core at the steel bearings - formed at the pour of the lift below	nr			30.00			**30.00**			£0.00	£0.00	**£0.00**	2 per beam - engineer
7B.27	Base plates / holding-down bolts to the SHS posts (on the B&B / pad foundations - engineer)	nr		10.00				**10.00**			£0.00	£0.00	**£0.00**	
7B.28	Green oak arched truss A1 (5 pieces: principal rafters, arch braces, collar), pegged, incl. fixings to the steel ridge / ICF bearings	nr					1.00	**1.00**			£0.00	£0.00	**£0.00**	22.1 m of oak (model) - oak framer
7B.29	Green oak arched truss A2 (5 pieces: principal rafters, arch braces, collar), pegged, incl. fixings to the steel ridge / ICF bearings	nr					1.00	**1.00**			£0.00	£0.00	**£0.00**	17.9 m of oak (model) - oak framer
7B.30	Green oak arched truss A3 (5 pieces: principal rafters, arch braces, collar), pegged, incl. fixings to the steel ridge / ICF bearings	nr					1.00	**1.00**			£0.00	£0.00	**£0.00**	17.9 m of oak (model) - oak framer
7C	**Roof covering, rooflights, eaves and rainwater (NRM2 18 / 33 - package RFC)**													
	Slope area = plan at the fascia line x 1.221 (257.2 m2 plan -> 313.9 m2). Hips / ridges / valley from a straight-skeleton height field of the fascia-line outline (true lengths). Covering per the elevations: dark slate / tile (spec TBC) on battens + counter-battens on a vapour-permeable underlay. Rooflights: 6 Velux marked on the plan crops (TBC - sizes / models by the architect). Front canopy over the long glazing (elevation item 5) - PROVISIONAL.													
7C.1	Roof covering: dark natural slate / slate-look tile (spec TBC) incl. under-eaves and top courses, fixings	m2					313.95	**313.95**			£0.00	£0.00	**£0.00**	Order guide +10% = 345.3
7C.2	Treated battens 25 x 50 + counter-battens to the covering	m2					313.95	**313.95**			£0.00	£0.00	**£0.00**	Order guide +10% = 345.3
7C.3	Vapour-permeable roof underlay with laps	m2					313.95	**313.95**			£0.00	£0.00	**£0.00**	Order guide +15% = 361.0
7C.4	Ridges: dry-fix ventilated ridge system	m					32.82	**32.82**			£0.00	£0.00	**£0.00**	3 nr
7C.5	Hips: dry-fix hip system / mitred slate hips incl. hip irons (true length)	m					5.88	**5.88**			£0.00	£0.00	**£0.00**	1 nr
7C.6	Valleys: Code 5 lead / GRP valley on valley boards (true length)	m					4.99	**4.99**			£0.00	£0.00	**£0.00**	1 nr
7C.7	Verges at the W and SE gables: dry verge / mortar verge with undercloak over the timber cladding	m					21.02	**21.02**			£0.00	£0.00	**£0.00**	
7C.8	Eaves: fascia, ventilated soffit (250 overhang), eaves tray / comb	m					60.54	**60.54**			£0.00	£0.00	**£0.00**	Fascia line
7C.9	Soffit boarding to the roof outside the walls (eaves overhang + the NE set-back areas under the PFC eaves beams)	m2					15.87	**15.87**			£0.00	£0.00	**£0.00**	Roof outline at the fascia less the ICF footprint
7C.10	Eaves gutters (aluminium, RAL 7016 to match) incl. stop ends, outlets, brackets	m					60.54	**60.54**			£0.00	£0.00	**£0.00**	Order guide +5% = 63.6
7C.11	Downpipes (RWP) from the gutters to the drainage, incl. shoes / offsets	nr					8.00	**8.00**			£0.00	£0.00	**£0.00**	RWPs marked on the plan crops - drainage design
7C.12	Rooflights (Velux or equal) incl. flashing kits, linings and blinds - 6 nr on the plan (TBC)	nr					6.00	**6.00**			£0.00	£0.00	**£0.00**	Count / sizes TBC - architect
7C.13	Chimney stack: lead back gutter, soakers + stepped cover flashings / apron at the roof intersection; stack capping / cowl	m					5.46	**5.46**			£0.00	£0.00	**£0.00**	Stack perimeter at the roof - flue height RFI (Approved Document J)
7C.14	Front canopy over the long glazing (elevations item 5): frame, covering, gutter - PROVISIONAL	item									£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Not modelled
7D	**Roof insulation and VCL (NRM2 18 / 28 - package RFC)**													
	WARM vaulted roof (rooms open to the rafters): insulation between + under the rafters with a VCL on the warm side, measured on the slope over the internal plan (212.3 m2 x 1.221); build-up and U-values by the SAP assessor (Approved Document L). Linings in Bill 2B.													
7D.1	Insulation between the rafters + insulated board under the rafters (warm pitched roof)	m2					259.18	**259.18**			£0.00	£0.00	**£0.00**	Order guide +5% = 272.1
7D.2	Vapour control layer, taped laps and penetrations (rooflights, steels, oak, flue)	m2					259.18	**259.18**			£0.00	£0.00	**£0.00**	Order guide +10% = 285.1
7D.3	Fire stopping / insulation closers at the eaves over the ICF wall heads and round the flue (Approved Document J clearances)	item									£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount.

Ref	Description	Unit	FB footing	GF floor	L1 GF walls	L2 gables	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	5						Levels: FB = footing courses: one 8in Standard course per floor zone (lower -689, upper -231.8) on the strip footing (by others); GF = GF precast block & beam floor, both zones (by others) + the ground-floor items; L1 = GF walls, 6in XR35, 8 courses to the underside of the plate 3,341; L2 = raked gables W / SE, chimney stack to 6,541, NE vault upstands (6in XR35); RF = vaulted cut roof (35 deg), steels, oak

PACKAGE SUMMARY - Bill 7 Roof - Vaulted Cut Roof, Steels, Oak Trusses, Covering, Rooflights, Rainwater & Insulation (package RFS / STR / RFC; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
7A	Roof structure - vaulted cut roof (NRM2 16 - package RFS; roof designer / engineer)	£0.00	£0.00	**£0.00**
7B	Structural steel and oak (NRM2 14 / 16 - package STR; ENGINEER - INDICATIVE, sections not designed)	£0.00	£0.00	**£0.00**
7C	Roof covering, rooflights, eaves and rainwater (NRM2 18 / 33 - package RFC)	£0.00	£0.00	**£0.00**
7D	Roof insulation and VCL (NRM2 18 / 28 - package RFC)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 7, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 8 - Opening Schedule - Windows, Glazing Screens & External Doors (one line per opening)

21 openings from the BuildEase window fit, one line each incl. sills / thresholds, fixings, tapes and ironmongery (alu-clad RAL 7016, indicative). [NRM2 25 / package WIN]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB footing	GF floor	L1 GF walls	L2 gables	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	5						Levels: FB = footing courses: one 8in Standard course per floor zone (lower -689, upper -231.8) on the strip footing (by others); GF = GF precast block & beam floor, both zones (by others) + the ground-floor items; L1 = GF walls, 6in XR35, 8 courses to the underside of the plate 3,341; L2 = raked gables W / SE, chimney stack to 6,541, NE vault upstands (6in XR35); RF = vaulted cut roof (35 deg), steels, oak
	8A Opening schedule - one line per opening, incl. its accessories (NRM2 25 - package WIN; window / door supplier)													
	From the BuildEase window fit (lfw_fit.json, 21 items: 3 double door, 13 fixed screen, 2 composite door, 3 window) and the spec openings: structural opening (so) W x H, alu-clad RAL 7016, INDICATIVE products - the supplier confirms sizes on site. Each line includes the frame, glazing (toughened / laminated where critical - Part K), ironmongery, the aluminium sill / threshold, frame fixings into the ICF (frames tight to the back of the outer EPS), the INTERNAL illbruck ME110 air-seal tape, external sealant / compressible tape and trickle vents / ventilation per Approved Document F. Priced per opening - never per m2.													
8A.1	L1-DW-06: Aluminium lift-and-slide door, 2 leaves (PPC RAL 7016, low threshold, Part M), so 4,401 x 2,411, leaves 2120 / 2285, flush bolt / locking to the passive leaf; head 2,410 (lower zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.2	L1-DW-07a: Alu-clad timber floor-length glazing screen (RAL 7016, toughened / laminated DGU, lights <= 1,000), so 748 x 2,411, 1 bay, fixed; head 2,410 (lower zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.3	L1-DW-07: Aluminium lift-and-slide door, 2 leaves (PPC RAL 7016, low threshold, Part M), so 3,551 x 2,411, leaves 1695 / 2285, flush bolt / locking to the passive leaf; head 2,410 (lower zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.4	L1-DX-08: Composite external door, 48 slab, multi-point lock, vision panel (PAS 24), so 977 x 2,111, leaf 821 x 1985, lever / cylinder set, letter plate / numerals as required; head 2,710 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.5	L1-DW-09: Alu-clad timber floor-length glazing screen (RAL 7016, toughened / laminated DGU, lights <= 1,000), so 1,811 x 2,411, 2 bays, fixed; head 3,010 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.6	L1-DW-10a: Alu-clad timber floor-length glazing screen (RAL 7016, toughened / laminated DGU, lights <= 1,000), so 1,323 x 2,411, 2 bays, fixed; head 3,010 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.7	L1-DW-10b: Alu-clad timber floor-length glazing screen (RAL 7016, toughened / laminated DGU, lights <= 1,000), so 1,590 x 2,411, 2 bays, fixed; head 3,010 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.8	L1-DW-10c: Alu-clad timber floor-length glazing screen (RAL 7016, toughened / laminated DGU, lights <= 1,000), so 450 x 2,411, 1 bay, fixed; head 3,010 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.9	L1-DW-11a: Alu-clad timber floor-length glazing screen (RAL 7016, toughened / laminated DGU, lights <= 1,000), so 956 x 2,411, 1 bay, fixed; head 3,010 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.10	L1-DW-11b: Alu-clad timber floor-length glazing screen (RAL 7016, toughened / laminated DGU, lights <= 1,000), so 805 x 2,411, 1 bay, fixed; head 3,010 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.11	L1-DW-11c: Alu-clad timber floor-length glazing screen (RAL 7016, toughened / laminated DGU, lights <= 1,000), so 351 x 2,411, 1 bay, fixed; head 3,010 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.12	L1-DW-11x: Alu-clad casement window (RAL 7016), DGU, so 686 x 1,061, 1 light (opening), restrictors, internal window board in Bill 4; head 2,708 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.13	L1-DW-12: Alu-clad timber floor-length glazing screen (RAL 7016, toughened / laminated DGU, lights <= 1,000), so 1,601 x 2,411, 2 bays, fixed; head 3,010 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.14	L1-DW-13: Alu-clad timber floor-length glazing screen (RAL 7016, toughened / laminated DGU, lights <= 1,000), so 2,036 x 2,411, 2 bays, fixed; head 3,010 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.15	L1-DW-14: Alu-clad timber floor-length glazing screen (RAL 7016, toughened / laminated DGU, lights <= 1,000), so 2,036 x 2,411, 2 bays, fixed; head 3,010 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories

Ref	Description	Unit	FB footing	GF floor	L1 GF walls	L2 gables	Roof	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	1	5						Levels: FB = footing courses: one 8in Standard course per floor zone (lower -689, upper -231.8) on the strip footing (by others); GF = GF precast block & beam floor, both zones (by others) + the ground-floor items; L1 = GF walls, 6in XR35, 8 courses to the underside of the plate 3,341; L2 = raked gables W / SE, chimney stack to 6,541, NE vault upstands (6in XR35); RF = vaulted cut roof (35 deg), steels, oak
8A.16	L1-DW-15: Alu-clad timber floor-length glazing screen (RAL 7016, toughened / laminated DGU, lights <= 1,000), so 2,036 x 2,411, 2 bays, fixed; head 3,010 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.17	L1-DW-16: Alu-clad timber floor-length glazing screen (RAL 7016, toughened / laminated DGU, lights <= 1,000), so 2,036 x 2,411, 2 bays, fixed; head 3,010 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.18	L1-DX-01: Composite external door, 48 slab, multi-point lock, vision panel (PAS 24), so 1,061 x 2,111, leaf 905 x 1985, lever / cylinder set, letter plate / numerals as required; head 2,710 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.19	L1-DW-02: Alu-clad casement window (RAL 7016), DGU, so 1,161 x 1,061, 2 lights (opening), restrictors, internal window board in Bill 4; head 2,708 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.20	L1-DW-03: Alu-clad casement window (RAL 7016), DGU, so 910 x 1,061, 1 light (opening), restrictors, internal window board in Bill 4; head 2,708 (upper zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8A.21	L1-DW-04-05: Aluminium lift-and-slide door, 2 leaves (PPC RAL 7016, low threshold, Part M), so 4,499 x 2,411, leaves 2169 / 2285, flush bolt / locking to the passive leaf; head 2,410 (lower zone)	nr			1.00			**1.00**			£0.00	£0.00	**£0.00**	Supply + install complete with accessories
8B Items common to the openings (NRM2 25 - package WIN)														
8B.1	Steel mullion posts (SHS 100) in the large lift-and-slide openings DW-06 / DW-07 / DW-04-05 - see Bill 7B; frame coupling to suit	item									£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Coordination
8B.2	Overheating check (Approved Document O - large glazed areas) and solar-control glass if required; escape windows to the bedrooms (ADB)	item									£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Architect / M&E

PACKAGE SUMMARY - Bill 8 Opening Schedule - Windows, Glazing Screens & External Doors (one line per opening) (package WIN; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
8A	Opening schedule - one line per opening, incl. its accessories (NRM2 25 - package WIN; window / door supplier)	£0.00	£0.00	**£0.00**
8B	Items common to the openings (NRM2 25 - package WIN)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 8, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Schedule A - Areas: External Faces, Lining Zones, I

ICF face areas by finish / zone (component export), floor / ceiling / roof areas (LF2

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Level	Item	Source	Length m	Depth / width m	Area m2
FB	FB outer faces (8in Std footing courses)	LF_components.json			39.69
FB/L1	Below-ground outer faces (protection / DPM, Bill 6A.2)	components			53.67
FB/L1	Plinth band, ground (~-150) to each zone FFL (Bill 1A.5)	components	82.79	0.15	11.31
FB/L1	GF wall outer faces above FFL - timber cladding	components			174.24
L2	Gables + vault upstands outer faces - timber cladding	components			21.47
L2	Chimney stack outer faces outside the building - cladding	components			10.49
L1	Lining zone: GF ICF inner faces above FFL	components	80.30		148.13
L2	Lining zone: gable / upstand inner faces + stack face inside	components			39.96
GF	Lower zone B&B (at the bearing)	LF2_floors.json			67.35
GF	Lower zone insulation / screed (inside the ICF)	LF2_floors.json			63.21
GF	Upper zone B&B (at the bearing)	LF2_floors.json			158.63
GF	Upper zone insulation / screed (inside the ICF)	LF2_floors.json			149.10
L1	Building footprint (ICF outer faces)	LF2_spec chains	82.79		241.31
L1	Internal plan inside the ICF	derived	80.30		212.31
RF	Vaulted ceilings ON THE SLOPE (internal plan x 1.221)	derived			259.18
RF	Roof plan at the fascia line (250 overhang, none at the gables)	LF2_spec roof ring	60.54		257.17
RF	Roof ON THE SLOPE (covering)	derived			313.95
RF	Soffits outside the walls (overhang + NE set-backs)	derived			15.87

Ground ASSUMED ~150 below each zone FFL. Stack faces inside the building are in the lining zone.

Schedule B - Openings (spec openings + BuildEase window fit)

From LF2_spec.json (21 ICF openings) and lfw_fit.json (21 fitted items). Not priced - priced in Bill 8.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Level	Ref	Fit style	Zone	W mm	H mm	Head mm	Area m2	Fit so (W x H)	Product (indicative)
L1	L1-DW-06	double_door	lower	4400	2410	2410	10.60	4401 x 2411	Aluminium lift-and-slide / glazed doors (PPC RAL 7016, low t
L1	L1-DW-07a	fixed_screen	lower	747	2410	2410	1.80	748 x 2411	GF floor-length glazing screen (alu-clad RAL 7016, lights <=
L1	L1-DW-07	double_door	lower	3550	2410	2410	8.56	3551 x 2411	Aluminium lift-and-slide / glazed doors (PPC RAL 7016, low t
L1	L1-DX-08	composite_door	upper	976	2110	2710	2.06	977 x 2111	composite door (48 slab, multi-point lock, vision panel)
L1	L1-DW-09	fixed_screen	upper	1810	2410	3010	4.36	1811 x 2411	GF floor-length glazing screen (alu-clad RAL 7016, lights <=
L1	L1-DW-10a	fixed_screen	upper	1322	2410	3010	3.19	1323 x 2411	GF floor-length glazing screen (alu-clad RAL 7016, lights <=
L1	L1-DW-10b	fixed_screen	upper	1589	2410	3010	3.83	1590 x 2411	GF floor-length glazing screen (alu-clad RAL 7016, lights <=
L1	L1-DW-10c	fixed_screen	upper	450	2410	3010	1.08	450 x 2411	GF floor-length glazing screen (alu-clad RAL 7016, lights <=
L1	L1-DW-11a	fixed_screen	upper	956	2410	3010	2.30	956 x 2411	GF floor-length glazing screen (alu-clad RAL 7016, lights <=
L1	L1-DW-11b	fixed_screen	upper	804	2410	3010	1.94	805 x 2411	GF floor-length glazing screen (alu-clad RAL 7016, lights <=
L1	L1-DW-11c	fixed_screen	upper	350	2410	3010	0.84	351 x 2411	GF floor-length glazing screen (alu-clad RAL 7016, lights <=
L1	L1-DW-11x	window	upper	685	1060	2708	0.73	686 x 1061	Alu-clad casement window (RAL 7016), 1 light (1 opening)
L1	L1-DW-12	fixed_screen	upper	1600	2410	3010	3.86	1601 x 2411	GF floor-length glazing screen (alu-clad RAL 7016, lights <=

Level	Ref	Fit style	Zone	W mm	H mm	Head mm	Area m2	Fit so (W x H)	Product (indicative)
L1	L1-DW-13	fixed_screen	upper	2035	2410	3010	4.90	2036 x 2411	GF floor-length glazing screen (alu-clad RAL 7016, lights <=
L1	L1-DW-14	fixed_screen	upper	2035	2410	3010	4.90	2036 x 2411	GF floor-length glazing screen (alu-clad RAL 7016, lights <=
L1	L1-DW-15	fixed_screen	upper	2035	2410	3010	4.90	2036 x 2411	GF floor-length glazing screen (alu-clad RAL 7016, lights <=
L1	L1-DW-16	fixed_screen	upper	2035	2410	3010	4.90	2036 x 2411	GF floor-length glazing screen (alu-clad RAL 7016, lights <=
L1	L1-DX-01	composite_door	upper	1060	2110	2710	2.24	1061 x 2111	composite door (48 slab, multi-point lock, vision panel)
L1	L1-DW-02	window	upper	1160	1060	2708	1.23	1161 x 1061	Alu-clad casement window (RAL 7016), 2 lights (2 opening)
L1	L1-DW-03	window	upper	910	1060	2708	0.96	910 x 1061	Alu-clad casement window (RAL 7016), 1 light (1 opening)
L1	L1-DW-04-05	double_door	lower	4498	2410	2410	10.84	4499 x 2411	Aluminium lift-and-slide / glazed doors (PPC RAL 7016, low t

Heads above the lower FFL (datum 0). Alu-clad RAL 7016, indicative - the supplier confirms on site.

Schedule C - Key Quantities per Column

Reference only - the bills carry the priced quantities. Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Column	ICF outer face m2	ICF inner face m2	External finish m2	Wall linings m2	Ceilings m2	Floor m2	Door leaves nr	Partitions m2
FB	39.69	35.04	0.00	0.00	0.00	0.00	0	0.00
GF	0.00	0.00	0.00	0.00	0.00	212.31	0	0.00
L1	199.53	170.90	185.55	706.19	0.00	0.00	14	261.97
L2	49.48	42.00	31.96	39.96	0.00	0.00	0	0.00
RF	0.00	0.00	0.00	0.00	259.18	0.00	0	0.00
Total	**288.70**	**247.94**	**217.51**	**746.15**	**259.18**	**212.31**	**14.00**	**261.97**

ICF faces from the Report Tool component export (570 forms). External finish: cladding + plinth (FB / L1), cladding incl. the stack (L2).

Schedule D - Partition Schedule (indicative, as modelled)

From the structure dump "LF Partitions" (lf2_partitions.rb, traced from the LR Design buildability plan). Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model (rebuilt 02.11.2026) of the client's planning / buildability drawings (LR Design: GF plan, elevations, sections C-C / D-D) and M. Whalley's levels sketch of 01.11.2026; no allowance for waste is included unless stated. Quantity columns are FB (footing courses) / GF (block & beam floor) / L1 (GF walls) / L2 (gables, stack, upstands) and the Roof; the Site total is their sum. Rates and amounts are by others.

Type	Run	Length mm	Thk mm	Base z	Top z	Area m2 (one face)	Build-up
A	A1 kitchen / utility	3649	140	-232	6,068	18.33	TYPE A 140 dense blockwork (load-bearing / step walls), rising to the vault (rafter underside)
A	A2 kitchen / lounge + hall	6256	140	-232	6,068	38.01	TYPE A 140 dense blockwork (load-bearing / step walls), rising to the vault (rafter underside)
A	A3 kitchen / pantry	3035	140	-232	5,638	14.59	TYPE A 140 dense blockwork (load-bearing / step walls), rising to the vault (rafter underside)
A	A4 hall / WC	3583	140	375	5,607	16.22	TYPE A 140 dense blockwork (load-bearing / step walls), rising to the vault (rafter underside)
A	A5 link west	1940	140	375	5,916	9.43	TYPE A 140 dense blockwork (load-bearing / step walls), rising to the vault (rafter underside)
A	A6 corridor	7394	140	375	4,557	30.50	TYPE A 140 dense blockwork (load-bearing / step walls), rising to the vault (rafter underside)
A	A7 sleeper / link	2954	140	375	5,797	14.56	TYPE A 140 dense blockwork (load-bearing / step walls), rising to the vault (rafter underside)
A	A8 bed 1 west	4885	140	375	5,842	22.64	TYPE A 140 dense blockwork (load-bearing / step walls), rising to the vault (rafter underside)
A	A9 wing corridor	3424	140	375	4,866	14.58	TYPE A 140 dense blockwork (load-bearing / step walls), rising to the vault (rafter underside)
A	A10 ensuite	3858	140	375	5,809	17.94	TYPE A 140 dense blockwork (load-bearing / step walls), rising to the vault (rafter underside)
A	A11 ensuite south	2532	140	375	4,432	10.27	TYPE A 140 dense blockwork (load-bearing / step walls), rising to the vault (rafter underside)
A	A12 ICF return? (RFI)	1176	140	375	4,805	4.81	TYPE A 140 dense blockwork (load-bearing / step walls), rising to the vault (rafter underside)
B	B1 utility	2538	100	375	6,019	12.07	TYPE B 100 blockwork, rising to the vault
B	B2 utility	1561	100	375	4,242	6.04	TYPE B 100 blockwork, rising to the vault
B	B3 utility	1041	100	375	4,242	3.65	TYPE B 100 blockwork, rising to the vault
C	C1 store	657	100	600	3,137	1.67	TYPE C timber stud 70 (100 overall) to the 2,537 suspended ceiling
C	C2 WC	2197	100	600	3,137	5.57	TYPE C timber stud 70 (100 overall) to the 2,537 suspended ceiling

Type	Run	Length mm	Thk mm	Base z	Top z	Area m2 (one face)	Build-up
C	C3 cloaks	664	100	600	3,137	1.68	TYPE C timber stud 70 (100 overall) to the 2,537 suspended ceiling
C	C4 bath	2885	100	600	3,137	7.32	TYPE C timber stud 70 (100 overall) to the 2,537 suspended ceiling
C	C5 bath	2128	100	600	3,137	5.40	TYPE C timber stud 70 (100 overall) to the 2,537 suspended ceiling
D	D1 link	2636	146	600	3,137	6.69	TYPE D timber stud 146 to the 2,537 suspended ceiling
S	S1 sleeper wall (under B&B)	6203	140	-689	-382	1.90	TYPE S1 blockwork sleeper wall under the lower-zone B&B

Blockwork 49.8 m, studs 11.2 m, sleeper wall 6.2 m. Raked heads follow the vault (rafter underside).